

# **JAMIA HAMDARD**

**Hamdard Nagar**  
**New Delhi-110062**

**02/05/2014**

## **Tender Notice** **Short Term**

Sealed item rate quotation in the prescribed format are hereby invited from the reputed/approved agency for the Electrical works for the up-gradation/renovation of electrical works at Virology Lab, D/o-Microbiology, HIMSR Building, Jamia Hamdard, Hamdard Nagar, New Delhi-110062.

The interested parties are required to possess the necessary Tools & expertise for the proper execution of the job. They should also have the PAN, TIN/WCT documents and work experience of similar works, in Govt./Semi Govt./State Govt. agencies/department etc. The interested parties are required to produce documentary evidence in support of the above. The BOQ and documents will be uploaded on the Website of Jamia Hamdard w.e.f. **02-05-2014 to 09-05-2014**.

<b>Name of work</b>	:	Up-gradation/renovation of electrical works etc
<b>Estimated Cost</b>	:	Rs. 1.20Lakh
<b>EMD Cost</b>	:	Rs. 2,000.00
<b>Place of work</b>	:	Virology Lab, D/o-Microbiology at HIMSR Building
<b>Time of completion</b>	:	10days

The quotations shall be deposited in **Tender Box** kept in the **Purchase Section** by 3:00pm of **09-05-2014** and will be opened at 3.30pm on the same day in the presence of the committee members and interested parties in the office of Executive Engineer (Officiating), basement, F/o-Science Building. Incomplete tender documents are liable to be rejected.

**(Dr. Firdous A. Wani)**  
Registrar

### **C.C.to:**

- P.A. to Registrar for kind information please
- P.A to Finance Officer for kind information please
- P.A. to Dean, HIMSR for kind information please
- HOD, Microbiology for kind information please
- Estate Officer
- J.E. (Electrical)
- Computer Centre (for display at website)

**Office of the Executive Engineer (Officiating)**  
**Jamia Hamdard, Hamdard Nagar**  
**New Delhi-110062**

**Dated: 02/05/2014**

To,

.....  
.....  
.....  
.....

Sealed item rates quotations are invited for the following electrical works for the up-gradation/renovation of electrical works at Virology Lab, D/o-Microbiology, HIMSR Building, Jamia Hamdard, Hamdard Nagar, New Delhi-110062. The agency having sufficient experience of such works in any academic institute and having TIN/WCT may only apply.

S.No.	Particular	Qty	Rate	Amount
1.	Supply & Fixing of circuit wiring with the following size PVC insulated copper conductor single core cable in surface/recessed PVC conduit alongwith same size earth wire completes in all respect.  (A) 2×2.5sqmm+1×2.5sqmm earth wire  (B) 2×4.0sqmm+1×4.0sqmm earth wire  (C) 2×6.0sqmm+1×6.0sqmm earth wire  (D) 2×10.0sqmm+1×10.0sqmm earth wire  <b>Make: Havells, Kalinga, Skytone</b>			
		65.0Rmt.		
		240.0Rmt		
		50.0Rmt.		
		32.0Rmt.		
2.	S/F 15/16Amp modular type power plug points accessories with modular 15/16Amp switch & outlet 3/5pin socket complete connection, testing &			

	commissioning etc. as required.  <b>Make: Anchor Roma</b>	25Nos.		
3.	S/F 5/6Amp modular type power light points accessories with modular 5/6Amp switch & outlet 3/5pin socket complete connection, testing & commissioning etc. as required.  <b>Make: Anchor Roma</b>	25Nos.		
4.	S/F of metal clad AC box with metal top and accessories along with on 32Amp MCB complete with connection testing as required.  <b>Make: ABB, Havells</b>	01Nos.		
5.	S/F following size SPN distribution board/double door 240 volts, sheet steel on surface/recessed complete with tinned copper bus bar, neutral bus bar, earth bar, inter connection, powder coated painted including earthing etc. as required.  (A) 4way sp double door  (B) 8way sp double door  (C) 12 Way TPN double door  <b>Make: ABB, Havells, Hagger</b>	01Nos  01Nos.  01Nos		
6.	P/F SP/TPN MCB/Isolator/MCCB/ELCB suitable for inductive load of following poles in the existing MCB distribution board complete with connections, testing and commissioning etc. as required.  (A) 6 to 32Amp single pole MCB  (B) 40Amp DP MCB	31Nos.		

	(C) 63Amp DP MCB  (D) 100 A TPN isolator  <b>Make: ABB, MDS, Hagger</b>	02Nos.  01Nos.  01Nos		
7	Supply and laying on surface 50 sq mm 3 ½core PVC insulated PVC sheathed alumuniam armoured xlpe cable of 1.1 KV grade  <b>Make: Havells, Skytone</b>	48.0Rmt.		
8	Making of cable end termination of 50 sq mm cable	02Nos.		
	<b>Total</b>			<b>Rs</b>

(Signature of the Contractor & Stamp)

**Note:-**

- Specification should be as mentioned on Annexure 'A'.
- The work should be taken up as per CPWD norms
- No minor should be engaged
- 5% security will be with held for six months which will be reckoned from the date of actual completion.
- Taxes will be deduct as per providing Govt. norms.
- Amount should be filled in digits & words clearly.

(Signature of the Contractor & Stamp)