

ANNEXURE "A"

BOQ/ Schedule of Qty.					
S.No.	Description of Items	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. sqm	sqm	500.00		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	500.00		
3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content, With water thinkable cement primer on wall surface having VOC content less than 50 grams/litre.	sqm	500.00		
4	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's				
4.a	One or more coats	sqm	1425		
4.b	Two or more coats	sqm	500		
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	sqm	200		
6	Dismantling of existing Pvc partition including disposal of unserviceable surplus material and stacking of serviceable material as directed by Engineer-in-Charge.	Sqm	25		
7	Providing and fixing of pvc (Semi Glazed) partitions,the partition frame will be made of mild steel tube of size 50x25x1.2mm .The vertical & horizontal members duly welded shall be placed 710mm to 950mm apart. The partition frame will be securely fixed to the walls , floors & ceiling . partition contains middle part of plain glass of 5 mm thick up to 940mm Hight and top and bottom part of PVC of Hight 840mm to 890mm. The frame will be painted with one coat of primer & two coats of synthetic enamel paint of approved colour& quality.Then PVC angle of size of 22x15 mm will be fixed to the frame outside ,The frame with the help of pvc beading of size 10x10 mm will be fixed inside the frame which will be filled with pvc hollow multi chamber section of size 200x20mm make polytech (BPI)/plasopan.	Sqm	40		
8	Providing and fixing of pvc door frame ,middle rail and hardware fittings .	Sqm	2.5		

9	Spray painting with synthetic enamel paint after sand papring with water proof sand paper ,filling N.C.putty in gaps hols etc. In interior and exterior sides on pvc partition	Sqm	100		
10	Providing & fixing PVC flooring of 1.5 mm thick approved quality in required shade and coloured (as per approved sample). The PVC flooring shall be fixed with required quality of rubber adhesive etc complete	Sqm	250		
11	Providing and fixing 18 mm thick gang saw cut, mirror polished, remoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble/ Udaipur	Sqm	3		
12	Providing and fixing stainless steel fasters with washers of required size & shape in existing stone cladding including drilling necessary hole in stones and embedding the fasnters. Including scaffoldings and POP applying to all cladding to avoid damage of cladding due to drill machine vibrations, cleaning cladding and site after completion of work.	each	110		
13	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	sqm	12		
14	Renewal of old putty of glass panes (length)	meter	30		
Total amount (Rs.) i/c GST					

(Signature & Seal of the Contractor)

