

Office of the Executive Engineer (E&M)

Jamia Hamdard

Hamdard Nagar, New Delhi-110062

Date: 20.02.2024

Corrigendum

This is with reference to the NIT ref no. *JH/E&M/fencing/Porta/Class rooms/CLB/23/21* dated 16.0.2024 for the work of ***fencing around newly constructed porta class rooms in front of Central Library Building***

It is hereby notified to all interested bidders that Price Bid is to be filled up in accordance to the updated BOQ attached herewith at Annexure 'A'. The tender will be opened on as per scheduled date & time of NIT earlier uploaded on the website at 3:30 PM in the office of Executive Engineer.

Azhar Ali Khan

Executive Engineer

Schedule of Quantities

S. N.	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil	17.22	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	21.01	Cum		
3	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	56.49	Sqm		
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.10.16.2 Hot finished seamless type tubes	3334.35	Kg		
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	10799.83	Kg		
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	70.00	Sqm		
7	Providing and fixing Pvc coated ms charling Jali for Fencing, Mesh Size: 25 X 25 mm, Wire Diameter: 2 mm or other suitable size mesh to be fixed & firmly anchored to the	660.94	Sqm		

	concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer-in-charge.				
8	<p>Landscaping of Area: Tentative leveling of surroundings of the porta classrooms by using Backhoe Loader & Excavator complete as required as per the Direction of Engineer in-charge</p> <p>Note: Bidders must visit and fully acquaint themselves with the nature of work before submitting the bids.</p>	01	Job		
	Total				
	Add GST 18%				
	Total amount i/c GST				
	Total in words				