

Price-Bid

Annexure "X"

Name of Work: Establishing of B.Sc. Clinical Research Lab, FYUP Deptt. of CTCR at 3rd floor SCLS Building.

S/No	Description	Qty	Rate	Amount (Rs.)
1	Providing & Fixing of WALL BENCH of size 7800L x 900B x 900H	1		
	Table Consisting of:-			
	Bottom Arrangements			
	Base Unit: 1 Door - 600mm	1	No(s)	
	Base Unit: 2 Door - 900mm	7	No(s)	
	Base Unit for Sink: 2 Door - 900 mm	1	No(s)	
	WSF Worktop Supporting Frame : 1500	5	Set(s)	
	Skirting PVC Skirting	1	Set(s)	
	ER Triangular Metal Electrical Raceway	7.8	Mtrs	
	EP Electrical Points on Raceway -5/15 Switch sockets (Without	12	No(s)	
	SD Service Dropper 200 X 120 X 2100mm	1	No(s)	
	RR 2 Tier Reagent Rack - 925 mm	4	Mtrs	
	RR 2 Tier Reagent Rack - 950 mm	2	No(s)	
	PPS PP Sink of Size: 600X450mm	1	No(s)	
WT3 3-way water tap	1	No(s)		
PB Peg /Drain Board with 20 pegs	1	No(s)		
WTG Jet Black Granite Work Top of 20 mm thick	78	Sqf		
1 JOB				
	Providing & installation of ISLAND BENCH of size (4800LX1500BX900H)mm with following items			
	Table Consisting of:			
	Base Unit: 1 Door 1 Drawer - 466mm	4	No(s)	

2	Bottom Arrangements	Base Unit: 2 Door - 900mm	4	No(s)	1 JOB		
		Base Unit for Sink: 2 Door -1400mm	1	No(s)			
		Leg Space Assembly with back panel	4	No(s)			
	BP	Blank Panelling	2	No(s)			
	PVC	PVC Skirting	1	Set(s)			
	EP	Electrical Points on Raceway -5/15 Switch sockets (Without wiring)	16	No(s)			
	SD	Service Dropper 200 X 120 X 2100mm	1	No(s)			
	RR	Reagent Rack Two Tier, with adjustable Glass Shelves, Pillar Assembly in GI Powder Coated, (black colour) removable Protection Steel Rods, Square Metal Electrical Raceway	4.8	Mtrs			
WTG	Jet Black Granite Work Top of 18 ± 1 mm thick	80	Sqf				
PPS	PP Sink of Size: 600X450mm	1	No(s)				
WT3	3-way water tap	1	No(s)				
3	Peroviding and fixing WALL BENCH/work stations of size (5900LX750BX750H)mm with following items						
	Construction C Frame						
		Table Consisting of:-					
		C-FRAME ASSEMBLY - 60 X	5	No(s)			
	Bottom Arrangements	Under Bench Cabinet on castors:	5	No(s)			
		Leg Space Assembly with back panel	5	No(s)			
BP	Blank Panelling	1	No(s)				

	EP	Electrical Pop up box with 2 nos 5/15A	5 Set(s)	1 JOB		
	SD	Service Dropper 200 X 120 X 2100mm	1 No(s)			
	CM	Cable Manager	5 No(s)			
	Writing Pad	Writing Pad	5 No(s)			
	WTG	Jet Black Granite Work Top of 18 ± 1 mm thick	49 Sqf			
4	WU900 - G	Providing & fixing of Wall Hanging Storage with GLAZED Door - 750× 600× 500 mm two door with one middle shelf & Lock	2 No(s)			
	GENERAL: item					
5	LOCKS	Providing & fixing of Locks for Cabinets/Drawers	30 No(s)			
6	SHELVES	Providing & fixing middle adjustable	21 No(s)			
	Total (Rs.)					
	<u>GST @ 18%</u>					
	Total (Rs.) (Including installation, freight insurance, i/c GST)					

