

Jamia Hamdard
Hamdard Nagar, New Delhi-110062
Spot Quotation Notice
For

Date: 28.04.2025

Name of work: Whitewashing & repairing work in room no. 426, AI Lab, 4th floor,
SEST, Central Library Building
Estimated cost: Rs. 22,289.00 (i/c GST)
Time of Completion: 07 days
Last date of submission 05.05.2025 upto 03:00 PM
Date of opening: 05.05.2025 at 03:30 PM

Terms and Conditions:

1. Quotations may be submitted latest by 05.05.2025 **upto 3.00 p.m.** in an envelope superscripting “**above mentioned work.**” and addressed to: **Executive Engineer, Jamia Hamdard , Hamdard Nagar, New Delhi-110062**
2. The rates/price quoted by contractor should be inclusive of all material cost, labour, services/tools, GST etc.
3. Work shall be done as per specification as specified in the BOQ. Work shall be completed within stipulated period failing which 1% penalty per week to maximum of 05% on the total work amount, shall be imposed.
4. Applicable taxes, [JHRW@0.25%](#) and other will be deducted as per Govt. norms.
5. No Escalation shall be considered during the execution period of the work.
6. Work shall be organized in such a manner which does not disturb the work of the University.
7. Payment shall be made after satisfactory completion of work.
8. Bidders are advised to visit the site first and submit their rates accordingly.

Azhar Ali Khan
Executive Engineer

Bill of Quantities

S.no	Description of item	Qty	Unit	Rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	10.00	Sqm		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	10.00	Sqm		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	110.00	Sqm		
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :1 Water thinnable cement primer	128.00	Sqm		
5	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour (with two or more coats)	128.00	Sqm		
6	Repairing of existing wooden work station by providing and fixing 19mm thick board/ ply with both side laminate of approximate size 3'x2'x3 and fixing of particle/ pin board size of 3'x2' covered with red color fabric etc complete as required.	1.00	Nos		
7	Re-fixing old glass panes with putty and nails	2.00	Sqm		
	Total amount				

Contractor Sign. with Seal