

Name of work: Providing and laying interlocking paver block in gym area at IBN E Sina				
S.no	Description of items	Qty	Unit	Rate
1	Surface dressing & levelling of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil sqm	133.00	sqm	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) cum	0.50	Cum	
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	133.00	sqm	
	Total			

(Signature of the Contractor & St

Annexure 'A'
Girls' Hostel
Amount

amp)